

CODDENHAM TREE SURVEY: MARCH 2023

SUMMARY OF PRIORITY OF WORKS – 2 year priority

TREE LOCATION	TREE #	PRIORITY	SURVEY COMMENT & RECOMMENDATION
Mill Hill	T5	2 years	Field Maple: the top of the tree is dead. Recommend coppice.
Broom Hill	T8	2 years	Common Oak: significant wound on north side of main stem. Lower wood is desiccated. Reactive callous growth present. Indicative decay extends down entire stem. Recommend reduce tree height to ~10m where lateral branches have live buds.
Broom Hill	T10	2 years	Sycamore: potential stem failure. Tree targets footpath. Recommend install dynamic fabric bracing system between 3 co-dominant stems.
Broom Hill	T11	2 years	Common Oak: tight union of co-dominant stems. Recommend reduce the spread of the lateral limb on the north side by ~1.5m to reduce lever arm force.
Broom Hill	T9	unspecified	Common Ash: significant dead wood and ivy in canopy. Recommend reduce limb with apical dieback over footpath to ~8m.